

SAN ANTONIO WATER SYSTEM <u>DOS RIOS WATER RECYCLING CENTER</u> <u>DIGESTER MIXING & SYSTEM ENHANCEMENTS PHASE 1</u> SAWS JOB NUMBER 07-6500

ADDENDUM NO. 7

August 9, 2010

To Bidder of Record:

This addendum, applicable to the project referenced above, is an amendment to the bidding documents and as such will be a part of and included in the Contract Documents. Acknowledge receipt of this addendum by entering the addendum number and issue date in the space provided in submitted copies of the proposal.

Clarifications:

Addendum No. 7 clarifies the response to Question 17 on Addendum No. 5.

The rehabilitation of concrete using Elastomeric polyurethane is not required under this contract. CONTRACTOR SHALL repair any digester concrete damaged by the construction activities to the same condition it was in before the damage.

Drawings:

- 1. Drawing 00-G-05, REPLACE general note no. 3 in its entirety with the following:
 - 3. CONTRACTOR TO REPLACE ALL EXISTING PAVED SURFACES IMPACTED BY PROJECT. PROVIDE NO LESS THAN 10 FEET IN LENGTH OR LESS THAN 10 FEET BETWEEN REPAIRED SECTIONS FROM EDGE OF PAVEMENT TO EDGE OF PAVEMENT USING 5" AC OVER 13" ABC OVER RECOMPACED SUBGRADE PER SPECIFICATIONS. USE TYPICAL DETAIL C130 FOR WOODEN BATTEN IF CONCRETE CURB IS NOT PRESENT. MAINTAIN CURRENT DRAINAGE PATTERN.

The remainder of the bid document remains unchanged.

The Contractor shall obtain the Record Drawings and Operations Maintenance Manuals from the San Antonio Water System prior to commencing the improvement activities required under this Project.

This Addendum, including this page, is two (2) pages in its entirety.

Each bidder is requested to acknowledge receipt of	this Addendum No. 7 by his/her signature
affixed hereto and to file same as an attachment to	nis/her bid.
R.E. KILIAN 94203 8 1/CENS	
7422.5	/09/10
Project Manager	
Carollo Engineers, Inc.	
The Undersigned acknowledges receipt of this Addend accordance with the information and stipulation set for	
Date Sign	nature of Bidder

END OF ADDENDUM