



Probandt Replacement Project (E Lachappelle to Oelkers)

SAWS construction work on this project will install approximately 744 LF of 10-inch gravity sewer mains and relocate of 1,345 LF of 4-inch to 16-inch water mains in one location within the Central Sewershed. This project is part of the work required by San Antonio's agreement with the EPA to rehabilitate deteriorated sewer infrastructure across the city.

When Will Work Occur?

Construction is planned for 2024. Estimated construction duration is 300 calendar days.

Construction Elements:

- ✓ This project will address sewer mains in need of repair based on condition assessment and will also replace associated manholes.
- ✓ Construction of this project will be in the Central Sewershed within the City of San Antonio.
- ✓ Installation of approximately 744 LF of 10-inch gravity sewer mains via Open Cut method and relocation of 1,345 LF of 4-inch to 16-inch water mains via Open Cut method.
- ✓ Construction within TxDOT and CoSA right of way.

For more information:

Engineering Contact

Alla Korostyshevsky
210-233-3447

SAWS Public Relations

Cecilia Picazo
210-233-3750

