



2020 SMP Package IV (Cadwallader St., Upson St.)
Solicitation Number: CO-00231
SAWS Job No.: 18-5013 & 18-5513

ADDENDUM 1
November 26, 2018

To Bidder of Record:

This addendum, applicable to work referenced above, is an amendment to the bid proposal, plans and specifications and as such will be a part of and included in the Contract Documents. Acknowledge receipt of this addendum by entering the Addendum number and issue date on the space provided in submitted copies of the bid proposal.

RESPONSES TO QUESTIONS

1. Question: What is the anticipated Award Date?

Response: It is anticipated that the contract will be awarded at the January 2019 Board Meeting.

2. Question: What is the anticipated Notice to Proceed Date?

Response: The Notice to Proceed Date is tentatively scheduled for February 2019. This is subject to change.

3. Questions: Bid Item No. 13W, 14W & 15W 6", 8" & 12" PVC Waterline (Fully Restrained). Please clarify, does this refer to the system to be restrained per SAWS Specs or does this mean 100% of all water pipe will restrained?

Response: Per Note 8 on the water plan sheets, the proposed water main shall be fully restrained. This refers to the entire length.

4. Question: If the proposed sewer lateral requires the existing curb, sidewalks or driveway to be removed and replaced, will this work be paid for under the appropriate concrete bid items for removing and replacing concrete?

Response: Yes, but only what is required by CoSA that is outside the lateral trench pay limits. Everything inside the trench pay limits is inclusive to the lateral (per payment section of SAWS Spec 854).

5. Question: On site specific submittals - concerning the bypass plan for these residential streets, will they be required to be created and stamped by a licensed engineer? Even though the liability is on the contractor regardless?

Response: Yes, bypass plan shall be produced and submitted following SAWS Spec 864-S1 which does require that the bypass pumping plan be signed and sealed by a professional engineer licensed in the State of Texas.

6. Question: Concerning SAWS' enforcement of the specifications as they pertain to payment. When will manholes be acceptable for payment?

Response: Manholes will be paid once they are installed, vacuum tested per SAWS Spec 852.6.

7. Question: Concerning SAWS' enforcement of the specifications as they pertain to payment. When will water main be acceptable for payment? After installation? Approved densities? Temporary pavement repair? Permanent ditch patch?

Response: Water mains will be acceptable for payment after installation, approved densities, all-weather surface, and hydrostatic testing have been completed.

8. Question: Concerning SAWS' enforcement of the specifications as they pertain to payment. When will fire hydrants/gate vales be acceptable for payment?

Response: Fire hydrants and gate valves will be acceptable to payment after the system has been installed and hydrostatically tested.

9. Question: Concerning SAWS' enforcement of the specifications as they pertain to payment. When will sewer main be acceptable for payment? After installation? Approved densities? Temporary pavement repair? Permanent ditch patch?

Response: Sewer mains will be acceptable for payment after installation, approved densities, and all-weather surfaces have been completed. Please note that payment does not constitute acceptance of systems. All required incidentals and other requirements such as Mandrel test, final trench restoration, I&I Barrier, etc. in SAWS Specifications must be completed prior to Final Acceptance.

10. Question: Where is Bid Item 5S Hot Mix Asphalt B (4 Inch) to be used at? What are the pay limits

Response: Hot Mix Asphalt B (4inch) is to be used along Upson St from STA 8+80 to MH U2-3 at the Dead End. The trench repair detail on Sheet 10 shows flowable fill, 4" TY B, and 2" TY D through these limits.

11. Question: How will the pavement repair be paid for removing the 1092 LF of AC Main?

Response: Pavement repair for the removal of AC main has been quantified and included in the total pavement quantities shown in the plans. The pavement repair for AC removal overlaps along Cadwallader Street where we 1' offset and nearly replacing in place. Additional quantities have been included along Upson Street. Payment shall be per the specification for HMA TY B (10"), HMA TY D (2"), and Tack Coat.

12. Question: There are items in the water bid schedule for removing and replacing sidewalks, driveways and curb. Will these items be paid for regardless if it's the main or water services that cause the removal and replacement of these items?

Response: Yes, but only what is required by CoSA that is outside the pipe/service/stem trench pay limits. Everything inside the trench pay limits is inclusive to the main, service and/or fire hydrant (per payment section of SAWS Spec).

CHANGES TO THE SPECIFICATIONS

1. No changes to the Specifications will result by this addendum.

CHANGES TO THE PLANS

1. No changes to the plans will results by this addendum.

END OF ADDENDUM

This Addendum, including this one (1) page, is three (3) pages with attachments in its entirety.

Attachments: None



Carlos Luna III

Carlos Luna III, P.E.
Maestas & Associates, LLC