



Multiple Sewershed Package 9
Solicitation Number: CO-00218-SM
Job No.: 17-4558

ADDENDUM 3
March 25, 2019

To Bidder of Record:

This addendum, applicable to work referenced above, is an amendment to the bidding documents and as such will be a part of and included in the Contract Documents. Acknowledge receipt of this addendum by entering the Addendum number and issue date on the space provided in submitted copies of the proposal.

CLARIFICATION:

Response to Question No. 7 included in Addendum 2 has changed to state that hydrostatic testing is required.

RESPONSES TO QUESTIONS:

Remove Response to Question No. 7 included in Addendum 2 and Replace with the Following:

Response: Vacuum testing and holiday testing are both required. Refer to SAWS Special Specification Item 910 Manhole Rehabilitation. Hydrostatic testing is required. Refer to SAWS Special Specification Item 910 Manhole Rehabilitation and TCEQ 217.57.

MODIFICATIONS TO SPECIFICATIONS

Special Provisions to the Technical Specifications:

Remove Page SPTS-3 from the Special Provisions to the Technical Specifications and replace with the revised Page SPTS-3 attached to this Addendum, addressing the change that hydrostatic testing is required.

This Addendum, including this one (1) page, is 2 pages total with attachment in its entirety.

Attachment

Special Provisions to the Technical Specifications, page SPTS-3

March 25, 2019

Date

CDS Muery F-1733



Curt W. Raabe
3/25/2019

Signature

END OF ADDENDUM 2

- *Quadex Aluminaliner*

Epoxy coating: *With specified thickness application.*

- *Raven 405 Series High Build Epoxy Liner: Required thickness 125 mils*
- *Carboline Plasite 4500: Required Thickness 125 mils*

All other language in this specification 910 remains in full force.