SAN ANTONIO WATER SYSTEM 2013 SMALL DIAMETER REHAB PROGRAM – PROJECT 6 SAWS JOB NO. 13-4813 SAWS SOLICITATION NO. B-13-CD-053-DD

ADDENDUM NO. 1 October 22, 2013

This addendum, applicable to work designed above, is an amendment to the bidding and specification documents and as such shall be a part of and included in the Contract Documents. Acknowledge receipt of this addendum by entering the addendum number and issue date in the spaces provided on all submitted copies of the proposal.

Addenda Purpose:

1.0 MODIFICATIONS TO SPECIFICATIONS:

- Replace SC-5.0 CONSENT DECREE NOTICE PROVISION with attached revision.
- Revised Specification 865 Sewer Main Pre-Television Inspection remove and replace in its entirety.

2.0 MODIFICATIONS TO PLANS:

- Work Order #3, Sheet 3 or 4 remove and replace.
- Work Order #6, Sheet 3 of 3 remove and replace.
- Work Order #7 remove and replace in its entirety.

3.0 TO PROVIDE NOTES FROM PRE-BID MEETING:

• Meeting Notes are attached for information only. The pre-bid meeting sign-in sheet has been posted previously on the SAWS website.

ACKNOWLEDGEMENT BY BIDDER

Each bidder is requested to acknowledge receipt of this Addendum No. 1 by his/her signature affixed hereto and to file same and attach with his/her bid.

The undersigned acknowledges receipt of this Addendum No. 1 and the bid submitted herewith is in accordance with the information and stipulations set forth.

DATE
SIGNATURE
END OF ADDENDUM NO. 1

Addendum 1

AD 1-1

SPECIAL CONDITION

SC-5.0 CONSENT DECREE NOTICE PROVISION

The San Antonio Water System ("SAWS"), the United States of America and the State of Texas have entered into a Consent Decree in Civil Action No. 5:13-cv-00666- DAE, United States of America and State of Texas v. San Antonio Water System, in the United States District Court for the Western District of Texas, San Antonio Division (the "Consent Decree"). A copy of the Consent Decree is available at

http://www.saws.org/Infrastructure/EPA/download.cfm

Work performed pursuant to this contract is work that SAWS is required to perform pursuant to the terms of the Consent Decree. In the event of any conflict between the terms and provisions of this Consent Decree Notice Provision and any other terms and provisions of this Contract or the Contract Documents, the terms and provisions of this Consent Decree Notice Provision shall prevail.

A. Retention of documents.

Contractor shall retain and preserve all non-identical copies of all documents, reports, research, analytical or other data, records or other information of any kind or character (including documents, records, or other information in electronic form including, but not limited to e-mails) in its or its sub-contractors' or agents' possession or control, or that come into its or its sub-contractors' or agents' possession or control, and that relate in any manner to this contract, or the performance of any work described in this contract (the "Information"). This retention requirement shall apply regardless of any contrary corporate or institutional policy or procedure or legal requirement. Contractor, Contractor's sub-contractors and agents shall retain and shall not destroy any of the Information until such time as Contractor has received written approval from the General Counsel of SAWS that the Information or any part of the Information may be destroyed. Contractor shall, within 30 days after receipt of a written request by SAWS, deliver the Information to SAWS. Contractor shall instruct and require its agents and sub-contractors performing any part of the work described in this contract to comply with the requirements of this paragraph.

B. Notification of events that may cause delay.

If any event occurs that may delay performance by Contractor, or Contractor's agents or sub-contractors of any work or obligation of any kind under this contract, Contractor shall provide notice in accordance with the Notice Provisions of this contract to SAWS within two (2) business days of the date Contractor or Contractor's agents or sub-contractors first knew that the event might cause a delay. Contractor shall provide a written explanation and description of the reasons for the delay, the anticipated duration of the delay, all actions taken or to be taken to

prevent or minimize the delay, and a schedule for implementation of any measures to be taken to prevent or mitigate the delay or the effect of the delay. **TIME IS OF THE ESSENCE** in the performance of the requirements of this paragraph and of any work to be performed by the Contractor in this contract.

C. Liability for stipulated penalties.

The Consent Decree provides that the United States of America, the United States Environmental Protection Agency and the State of Texas may assess stipulated penalties against SAWS upon the occurrence of certain events. To the extent that Contractor or Contractor's agents or sub-contractors cause or contribute to, in whole or in part, the assessment of any stipulated penalty against SAWS, Contractor agrees that it shall pay to SAWS the full amount of any stipulated penalty assessed against and paid by SAWS that is caused or contributed to in whole or in part by any action, failure to act, or failure to act within the time required by any provision of this contract. Contractor shall also pay to SAWS all costs, attorney fees, expert witness fees and all other fees and expenses incurred by SAWS in connection with the assessment or payment of any such stipulated penalties, or in contesting the assessment or payment of any such stipulated penalties. In addition to any and all other remedies to which SAWS may be entitled at law or in equity, Contractor expressly authorizes SAWS to withhold all amounts assessed and paid as stipulated penalties, and all associated costs, fees, or expenses from any amount unpaid to Contractor under the terms of this contract, or from any retainage provided in the contract.

ITEM 865 SEWER MAIN PRE-TELEVISION INSPECTION

866.1 DESCRIPTION:

The Contractor shall furnish all labor, materials, equipment, and incidentals to provide the televising and NASSCO-(PACP) standard video, recorded in MPEG-1 format and written to DVD/CD video of sewer lines and manholes utilizing a color, closed-circuit television inspection unit to determine their condition.

866.2 GENERAL:

Pre and Post televising of sanitary sewer mains shall be done immediately after cleaning sewer main. Televising shall be observed by SAWS Inspector and Contractor as the camera is run through the system. Any abnormalities such as, but not limited to, misaligned joints, cracked/defected pipe, rolled gaskets, shall be identified and logged by the Contractor. Sections requiring repair shall be retelevised to verify condition of repair. No additional compensation shall be provided for re-televising.

866.3 **EXECUTION:**

The Contractor shall provide DVD/CD and logs of the televised inspection for review. If the Contractor provided DVD/CD of such poor quality that it cannot be properly evaluated, the Contractor shall re-televise as necessary and provide a DVD/CD of good quality at no additional cost to SAWS. If the Contractor cannot provide a DVD/CD of such good quality that can be reviewed by SAWS, SAWS may elect to televise the line at the Contractor's expense.

The television unit shall also have the capability of displaying in color, on DVD/CD, pipe inspection observations such as pipe defects, sags, points of root intrusion, offset joints, service connection locations, and any other relevant physical attributes. Each tape shall be permanently labeled with the following:

Project name
Date of television inspection
Station to station location and size of sanitary sewer
Street/easement location
Name of Contractor
Date DVD/CD submitted
DVD/CD number

The Contractor shall provide a line diagram area sketch and written log for each completed segment of DVD/CD sewer main describing the section being televised, flow and camera direction, position of service connections, descriptions and

location of failures, pipe condition, weather conditions, and other significant observations.

The television inspection equipment shall have an accurate footage counter that displays on the monitor the exact distance of the camera from the center of the starting manhole. A camera with rotating and panning lens capabilities is required. The camera height shall be centered in the conduit being televised. The speed of the camera through the conduit shall not exceed 40 feet per minute.

The Contractor shall be required to have all materials, equipment, and labor force necessary to complete all video on the job site prior to isolating the sewer manhole segment and beginning video operations.

Television inspection shall be done one manhole section at a time and the flow in the section being televised shall be bypassed if the line is in service and the flow exceeds twenty-five (25%) of the internal pipe diameter. When the depth of flow at the upstream manhole of the manhole section being worked is above the maximum allowable for television inspection, the flow shall be reduced to allowable levels by temporarily plugging or blocking the flow or bypass pumping, as approved by SAWS.

The Contractor shall not be allowed to float the camera. There may be occasions during the televised inspection of a manhole section when the camera will be unable to pass an obstruction. At that time, and prior to proceeding, the Contractor shall contact SAWS Inspector. If the length of sewer line cannot be televised because of obstruction, the Contractor shall clean the system as is necessary. If, in the opinion of SAWS Inspector, the obstruction is attributed to a collapsed main or pipe deflection, televising shall be suspended, payment shall be made based on the actual televised length, and the remaining televising of the sewer line shall be continued upon successful correction of the blockage by the Contractor. No additional payment shall be made for additional setups required due to obstructions encountered during televising.

The Contractor is solely responsible for any damage of sewer mains as direct result of televising operations. Any repair shall also be the responsibility of the Contractor. The method(s) used for securing passage of the camera are at the discretion of the Contractor, as approved by SAWS.

No separate and/or additional payment will be made for any excavation, man entry, or any other method that may be required to retrieve video equipment that may have been hung up, destroyed, and/or lost during the operation.

866.4 SEWER MAIN BYPASS PUMPING:

The Contractor shall perform flow management operations in accordance with Item No. 1001 and as outlined below.

The Contractor shall furnish all labor, supervision, tools, equipment, appliances, and materials to perform all operations in connection with bypass pumping of sewage flow for the purpose of preventing interference with the televising of the sanitary sewer manholes and mainlines as well as providing reliable sewer service to the occupants of the buildings being served.

The Contractor will be required to provide adequate pumping equipment and force mains in order to maintain reliable sanitary sewer service in all sanitary sewer lines involved in this project. The Contractor shall notify the Inspector should a surcharge occur during the televising process that results in overflows of sewage. In case of bypass equipment failure, the Contractor shall discontinue work and release sewer flows until such time as equipment failure is corrected. SAWS shall approve the location of the pump(s), force main(s), and discharge points. Under no circumstances shall the flow be interrupted or stopped, such that damage is done to either private or public property or sewage flows or overflows into a storm sewer or natural waterway.

The Contractor shall provide bypass pumping of sewage around each segment(s) of pipe that is to be televised and shall be responsible for all required bulkheads, pumps, equipment, piping, and other related appurtenances to accomplish the sequence of pumping. A qualified person shall man the pumps, on-site, at all times during the bypassing procedure.

All piping, joints, and accessories shall be designed to withstand the maximum bypass system pressure, or a minimum of 50 psi, whichever is greater. During bypass pumping, no sewage shall be leaked, dumped, or spilled into or onto any area outside of the existing sanitary sewer system. When bypass-pumping operations are complete, all piping shall be drained into the sanitary sewer prior to disassembly. The Contractor shall demonstrate that the pumping system is in good working order and can successfully handle flows during cleaning and televising operations, prior to commencing with the cleaning and televising of the system.

866.5 MATERIALS REQUIRED FOR BYPASS OPERATION:

The Contractor shall be required to have all materials, equipment, and labor necessary to complete the repair or replacement on the jobsite prior to isolating the sewer manhole or line segment and beginning bypass pumping operations.

866.6 TRAFFIC CONSIDERATIONS:

The Contractor shall locate bypass pumping suction and discharge lines so as to not cause undue interference with the use of streets, private driveways, and alleys to include the possible temporary trenching of force mains at critical intersections. Traffic management shall be done under the approval of respective City, County, or State Traffic, Barricade, and Signalization Departments. The Contractor shall not open cut existing streets to accommodate bypass-pumping piping unless specific written approval is given.

866.7 **PUMP OPERATIONS:**


The Contractor shall plug off and pump down the sewer manhole and/or line segment in the immediate work area and shall maintain the sanitary sewer system so that surcharging does not occur. The Contractor shall coordinate with all property owners to ensure that no damage will be caused to their property during any and all sewer rehabilitation work. The Contractor shall complete the televising as quickly as possible and shall satisfactorily meet all requirements prior to discontinuing bypass pumping operations and returning flow to the sewer manhole or line segment. The Contractor shall ensure that no damage will be caused to private property as a result of bypass pumping operations. Ingress and egress to adjacent properties shall be maintained at all times. Ramps, steel plates, or other methods shall be employed by the Contractor to facilitate traffic over surface piping. There will be no separate pay item for this work.


In the event that sewage accidentally drains into the drainage system or is spilled within the project, the Contractor shall <u>immediately</u> stop the overflow, notify SAWS Inspector, and take the necessary action to clean up and disinfect the spillage using an HTH or equal chemical at no additional cost to SAWS.

866.8 <u>MEASUREMENT AND PAYMENT:</u>

Measurement and payment for pre-television inspection will be made for the work to be done on the basis of the unit bid price per **linear foot** of the pipe diameters specified. Payment shall be considered full compensation for all labor, materials, equipment, tools, logging, by pass pumping and incidentals necessary to complete the work.

Payment per linear foot shall include pre-television inspection of the pipe segment being rehabilitated. Post-television inspection will not be measured or paid for separately, but shall be considered subsidiary to other rehabilitation bid items.





UNDERGROUND ELEC. ----- UE --

REPLACEMENT &

IMPROVEMENTS

SHEET

Contractor must notify and/or contact SAWS Inspections at 233-3500 and SAWS Engineering at 233-3493 48 hours before any of the following activities take place.

NOTE: CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE

SIZES AND GRADES BEFORE START OF CONSTRUCTION. (N.S.P.J.)

- 1. Notification of Pre-Television Inspection.
- 2. Notification of Bypass Pumping setup operations.
- 3. Notification of the Pipe installation.

SAN ANTONIO WATER SYSTEM

REPLACEMENT & IMPROVEMENTS



JOB NO. 13-4813 W.O. #7, D.R. #367



BEECHWOOD LANE - 8" SANITARY SEWER REHAB PROJECT (2013 SMALL DIAMETER REHAB PROGRAM - PROJECT 6)

GENERAL NOTES

1. All materials and construction procedures within the scope of this contract shall be approved by the San Antonio Water System (SAWS) and comply with the following as applicable:

A. Current Texas Commission on Environmental Quality Design Criteria for Sewerage Systems [31 TAC 217.1, 31 TAC 217.2, 31 TAC 217.3, and 31 TAC 217.13 and 2131.

- B. Current TXDOT "Standard Specifications for Construction of Highways, Streets and Drainage."
- C. Current "San Antonio Water System Standard Specifications for Construction."
- D. Current City of San Antonio "Standard Specifications for Public Works Construction."
- E. Current Bexar County Specifications.
- F. Current City of San Antonio "Right of Way Management and Criteria Manual".
- 2. The Contractor/Foreman is to notify and make arrangements with the SAWS Construction Inspector Division at 233-3500 and involve the home resident and/or property owners 48 hours prior to excavation.
- 3. The existence and location of underground utilities indicated on the plans are taken from the best records available and are not guaranteed to be accurate. The Contractor/Foreman is responsible for maintaining, supporting, and protecting the integrity of underground utilites and power poles during construction, and is required to call the following numbers 48 hours before beginning any excavation.

San Antonio Water System 233-2010
Storm Water Engineering 207-5009
COSA Traffic Signal Operations 207-7720
Texas State Wide One Call Locator 1-800-545-6005

- 4. If damaged, the Contractor/Foreman shall be responsible for restoring existing fences, curbs, streets, driveways, sidewalks, landscaping, structures, etc. to its original or better condition. (No Separate Pay Item)
- 5. Trench excavation protection shall be accomplished as required by the provisions of Part 1926, Subpart P-Excavation, Trenching and Shoring of The Occupational Safety and Health's Standards and Interpretations, The Contractor shall also comply with the provisions included in Item 550, Trench Excavation Safety Protection, of the current San Antonio Water System Specifications for Water and Sanitary Sewer Construction.
- 6. The Contractor/Foreman shall avoid cuting roots larger than one inch in diameter when excavating near existing trees. Excavation in vicinity of trees shall proceed with caution. The Contractor/Foreman shall contact the City Arborist at 207-8053 for guidance.

EDWARDS AQUIFER RECHARGE ZONE


NE

LOOP 410


ATASCOSA CO


PROJECT SITE

VICINITY MAP



LOCATION MAP





SANDRA L. GOMEZ

98284

10 23 13

- PIPE BURST 842 L.F. OF 8" PIPE

Contractor must notify and/or contact SAWS Inspections at 233-3500 and SAWS Engineering at 233-3493 48 hours before any of the following activities take place.

- 1. Notification of Pre-Television Inspection.
- 2. Notification of Bypass Pumping setup operations.
- 3. Notification of the Pipe installation.

NOTE: CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE SIZES AND GRADES BEFORE START OF CONSTRUCTION. (N.S.P.J.)

LEGEND	2013
PROP. SAN SEWER	2013
EXISTING SAN. SEWER ———————————————————————————————————	,
WATER MAIN	
GAS MAIN2"G	B
STORM SEWER -24"ST-0-	DN: M.R.
EXISTING UTILITY POLE	DR: M.R. CK: S.L.C
UNDERGROUND ELEC. —— UE ———	CK: S.L.C
UNDERGROUND TELE. ———————————————————————————————————	BLK. MA 158,160-60

JOB NO. 13-4813 2013 SMALL DIAMETER REHAB PROGRAM - PROJECT 6 W.O.*7

\mathbf{BE}	ECH	WOO	D	LN.	

.R. .R. L.G. L.G.	SAN ANTONIO WATER SYSTEM	DATE Feb. II, 2
IAP:	REPLACEMENT &	SHEET
-608	IMPROVEMENTS	2 0F



SCALE, IN FEET

- PIPE BURST 332 L.F. OF 8" PIPE

Contractor must notify and/or contact SAWS Inspections at 233-3500 and SAWS Engineering at 233-3493 48 hours before any of the following activities take place.

1. Notification of Pre-Television Inspection.

3. Notification of the Pipe installation.

2. Notification of Bypass Pumping setup operations.

NOTE: CONTRACTOR MUST FIELD VERIFY ALL DEPTHS, DISTANCES, PIPE SIZES AND GRADES BEFORE START OF CONSTRUCTION. (N.S.P.J.)

LEGEND	JOB NO. 13-4813		
PROP. SAN SEWER EXISTING SAN. SEWER ———————————————————————————————————	2013 SMALL DIAMETER REHAB PROGRAM - PROJECT 6 W.O.*7		
GAS MAIN ——2"G ——	BEECHWOOD LN.		
STORM SEWER —24"ST————————————————————————————————————	DN: M.R. DR: M.R. CK: S.L.G. CK: S.L.G. CK: S.L.G. SYSTEM DATE DATE Feb. II, 2013		
UNDERGROUND TELE. ———————————————————————————————————	BLK. MAP: REPLACEMENT & SHEET 160-608 IMPROVEMENTS 3 OF 3		

NON-MANDATORY PRE-BID MEETING NOTES SAN ANTONIO WATER SYSTEM 2013 SMALL DIAMETER REHAB PROGRAM – PROJECT 6 SAWS JOB NO. 13-4813 SAWS SOLICITATION NO. B-13-CD-053-DD

I. MEETING TIME/PLACE

- Wednesday, October 17, 2013, 10:00 a.m.
- SAWS, Tower II, Conference Room CR-C137

II. PROJECT DISCUSSION

- 1. This contract is part of the Consent Decree.
- 2. This is an emergency type contract so 48-hour response is expected on all work orders. 48- Hour mobilization will not be paid separately and shall be considered subsidiary to other bid items.
- 3. The intent of this contract is to rehabilitate sanitary sewer lines using trenchless methods.
- 4. All work orders shall be designed trenchless and the contractor that wins this work order contract is expected to perform a majority of the work.
- 5. The contractor is expected to maintain work on each work order until it's complete and multiple work orders may be issued at one time.
- 6. Please be familiar with SAWS standard specs and the specs for this contract.
- 7. Flow Management such as bypass pumping is subsidiary to other bid items.
- 8. Contract duration for these work orders will have a short time frame.
- 9. The contractor will be responsible for applying and obtaining CoSA ROW street cut permits and all fees associated with permits.
- 10. Please be sure to read the supplemental conditions and the special conditions.
- 11. Work performed pursuant to this contract is work that SAWS is required to perform pursuant to the terms of the Consent Decree between SAWS and the EPA.