

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

TIME & DATE: Job # 08-2512  
10:00 A.M.  
November 19, 2013

**BID REJECTED**

S J Louis Construction of Texas LTD  
9862 Lorene #200  
San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price	
1	2,980	LF	TRENCH EXCAVATION SAFETY PROTECTION	\$0.01	\$29.80
2	2,804	LF	54" DIAMETER GRAVITY SEWER. FRPM ASTM D-3262, SN 72. COMPLETE AND IN-PLACE. INCLUSIVE OF EXCAVATION, BEDDING, BACKFILL, DEWATERING AND TESTING.	\$611.00	\$1,713,244.00
3	58	LF	DUAL 42" FRPM ASTM D-3262, SN 72, INCLUSIVE OF JACKING 7 BORING, BORE PITS, DUAL 60" STEEL ENCASMENT PIPE & CASING SPACERS, ANNULAR GROUT, EXCAVATION, BEDDING, BACKFILL, DEWATERING, AND TESTING. COMPLETE AND IN-PLACE	\$3,024.00	\$175,392.00
4	176	LF	DUAL 42" FRPM ASTM D-3262, SN 72, INCLUSIVE OF EXCAVATION, BEDDNG, BACKFILL, DEWATERING, AND TESTING. COMPLETE AND IN-PLACE	\$540.00	\$95,040.00
5	223	LF	18" (DIPS) FUSIBLE PVC DR 25 AIR BYPASS VIA SLIPLINING OF EXISTING ABANDONED 24" SANITARY SEWER LINE. INCLUSIVE OF PRE-CLEANING AND PRE-TELEVISION INSPECTION OF EXISTING 24-INCH HOST PIPE. COMPLETE IN-PLACE	\$187.00	\$41,701.00
6	70	LF	18" (DIPS) FUSIBLE PVC DR 25 AIR BYPASS. COMPLETE IN-PLACE. INCLUSIVE OF 6" CONCRETE SLAB. CONNECTING TO EXISTING AND PROPOSED SEWER MANHOLES/JUNCTION BOXES, EXCAVATION, BEDDING, BACKFILL, DEWATERING, AND TESTING.	\$229.00	\$16,030.00

**BID REJECTED**

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

TIME & DATE: Job # 08-2512  
10:00 A.M.  
November 19, 2013

**BID REJECTED**

S J Louis Construction of Texas LTD  
9862 Lorene #200  
San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price	
7	1	LS	JUNCTION STRUCTURE JB-1 @STA 0+00. INCLUSIVE OF CONNECTION OF EXISTING 54' AND PROPOSED 54" SANITARY SEWER LINE, STRUCTURAL EXCAVATION, DEWATERING, MH RISERS/CONE/RING & COVER, COATING, FLOWABLE FILL, TESTING. COMPLETE AND IN-PLACE.	\$200,000.00	\$200,000.00
8	1	LS	JUNCTION STRUCTURE JB-2 @STA 20+49.40 (DOWNSTREAM SIPHON STRUCTURE). INCLUSIVE OF STAINLESS STEEL SLUICE GATES, TESTED BOTH SIDES, STRUCTURAL EXCAVATION, DEWATERING, MH RISERS/CONE/RING & COVER, COATING, FLOWABLE FILL, TESTING. COMPLETE AND IN-PLACE	\$275,000.00	\$275,000.00
9	1	LS	JUNCTION STRUCTURE JB-3 @STA 22+83.600 (UPSTREAM SIPHON STRUCTURE). INCLUSIVE OF STAINLESS STEEL SLUICE GATES, TESTED BOTH SIDES, STRUCTURAL EXCAVATION, DEWATERING, MH RISERS/CONE/RING & COVER, COATING, FLOWABLE FILL, TESTING. COMPLETE AND IN-PLACE	\$275,000.00	\$275,000.00
10	1	LS	JUNCTION STRUCTURE JB-4 @STA 30+37.79. INCLUSIVE OF CONNECTION OF EXISTING 48" SANITARY SEWER LINE, 54" STUBOUT AND PLUG, STRUCTURAL EXCAVATION, DEWATERING, MH RISERS/CONE/RING & COVER, COATING, FLOWABLE FILL, TESTING. COMPLETE AND IN-PLACE	\$200,000.00	\$200,000.00
11	1	EA	TEE BASE FIBERGLASS MANHOLE, ON 54" PIPE, WITH 54" LATERAL CONNECTION (@ STA 0+37.06) WITH 60" RISER. INCLUSIVE OF 54" STUBOUT AND CAP. COMPLETE AND IN-PLACE.	\$21,600.00	\$21,600.00

**BID REJECTED**

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

TIME & DATE: Job # 08-2512  
10:00 A.M.  
November 19, 2013

**BID REJECTED**

S J Louis Construction of Texas LTD  
9862 Lorene #200  
San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price		
12	6	EA	TEE BASE FIBERGLASS MANHOLE, ON 54" PIPE WITH 60" RISER. COMPLETE AND IN-PLACE.	\$20,000.00		\$120,000.00
13	1	EA	TEE BASE FIBERGLASS MANHOLE, ON 54" PIPE, WITH 18" AIR BYPASS CONNECTION (@25+49.70) WITH 60" RISER. COMPLETE AND IN-PLACE.	\$22,800.00		\$22,800.00
14	1	EA	TEE BASE FIBERGLASS MANHOLE, ON 54" PIPE, WITH 6" LATERAL CONNECTION (@28+23.35) WITH 60" RISER. COMPLETE AND IN-PLACE	\$19,500.00		\$19,500.00
15	32	VF	TEE BASE MH 60" RISER EXTRA DEPTH	\$1.00		\$32.00
16	134	LF	6" GRAVITY SEWER PIPE, PVC ASTM D-3034. INCLUSIVE OF EXCAVATION, BEDDING, BACKFILL, DEWATERING, ALL FITTINGS, CLEAN-OUTS, AND RESTORATION TO PRE-CONSTRUCTION CONDITIONS. COMPLETE AND IN-PLACE	\$91.00		\$12,194.00
17	2,618	LF	INSTALL 48" CIPP SANITARY SEWER PIPE, ALL DEPTHS. INCLUSIVE OF PRE-CLEANING AND PRE-TELEVISION INSPECTION.	\$356.00		\$932,008.00
18	158	LF	CLEANING OF EXISTING 2-42" SIPHON BARRLES. INCLUSIVE OF DEWATERING AND DEPOSIT REMOVAL	\$160.00		\$25,280.00
19	1	LS	UPSTREAM SIPHON STRUCTURE REHABILITATION INCLUSIVE OF STRUCTURAL HIGH-SULFATE RESISTANT LINING.	\$36,000.00		\$36,000.00
20	1	LS	DOWNSTREAM SIPHON STRUCTURE REHABILITATION INCLUSIVE OF LOCATING AND EXPOSING SIPHON STRUCTURE AND STRUCTURAL HIGH-SULFATE RESISTANT LINING	\$38,000.00		\$38,000.00
21	7	EA	ADJUSTING EXISTING MANHOLE-UPGRADE/REPLACE RING AND COVER	\$2,150.00		\$15,050.00
22	6	EA	MANHOLE REHABILITATION (ON EXISTING 48" SEWER)-STRUCTURAL HIGH-SULFATE RESISTANT COATING.	\$6,200.00		\$37,200.00

**ntage**

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
 SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

TIME & Job # 08-2512  
 10:00 A.M.

DATE: November 19, 2013

BID REJECTED

S J Louis Construction of Texas LTD  
 9862 Lorene #200  
 San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price	Perce	
23	1	LS	MANHOLE REHABILITATION (ON EXISTING 24" LINE)- INCLUSIVE OF CUTTING AND PLUGGING EXISTING 24" LINE, FILLING/GROUTING AND FORMING INVERT OF MANHOLE TO ELEVATION OF OUTGOING SERVICE AND STRUCTURAL HIGH-SULFATE RESISTANT COATING. COMPLETE AND IN-PLACE	\$5,000.00		\$5,000.00
24	3,272	LF	SEWER MAIN TELEVISION INSPECTION, PROPOSED LINE C	\$1.00		\$3,272.00
25	1	EA	OBSTRUCTION REMOVAL, INCLUSIVE OF REMOVAL OF ROOTS, 48" DIAMETER PIPE.	\$10,000.00		\$10,000.00
26	1	LS	ODOR CONTROL SETUP AND REMOVAL	\$10,000.00		\$10,000.00
27	1	LS	ODOR CONTROL EQUIPMENT RENTAL	\$5,000.00		\$5,000.00
28	1	LS	ODOR CONTROL BIOCHEMICAL SOLUTION.	\$5,000.00		\$5,000.00
29	1	LS	FLOW MANAGEMENT AND BYPASS PUMPING	\$35,000.00		\$35,000.00
30	1	LS	STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AND EXECUTION	\$500.00		\$500.00

BID REJECTED

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

TIME & DATE: Job # 08-2512  
10:00 A.M.  
November 19, 2013

**BID REJECTED**

S J Louis Construction of Texas LTD  
9862 Lorene #200  
San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price		
31	160	LF	CONCRETE CURB/STONE CURB	\$20.00		\$3,200.00
32	22	SY	CONCRETE SIDEWALKS.	\$60.00		\$1,320.00
33	1,350	SY	CUTTING AND REPLACING PAVEMENT, REPLACING WITH 10" ASPHALT TREATED BASE AND 2" HMAC SURFACE	\$106.00		\$143,100.00
34	1	LS	PRE- AND POST CONSTRUCTION VIDEO	\$500.00		\$500.00
35	1	LS	CONSTRUCTION PHOTOGRAPHY	\$500.00		\$500.00
36	10,000	SY	SODDING	\$5.00		\$50,000.00
37	1	LS	BARRICADES, SIGNS, AND TRAFFIC HANDLING INCLUSIVE OF HANDLING OF PEDESTRIAN/PARK TRAFFIC.	\$12,000.00		\$12,000.00
38	1	LS	SAFETY FENCING	\$20,000.00		\$20,000.00

Prepared by DYS

Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449  
 SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C

Job # 08-2512

TIME & 10:00 A.M.

DATE: November 19, 2013

**BID REJECTED**

S J Louis Construction of Texas LTD  
 9862 Lorene #200  
 San Antonio, Texas 78216

Item No.	Estimate Qty	Unit of Issue	Description	Unit Price		
39	2	EA	INLET PROTECTION	\$900.00		\$1,800.00
40	2,969	LF	TEMPORARY SEDIMENT CONTROL FENCE (SILT FENCE).	\$1.50		\$4,453.50
41	250	LF	ORGANIC FILTER TUBES.	\$8.00		\$2,000.00
42	1,111	SY	CONSTRUCTION EXITS (INSTALL/REMOVE).	\$8.00		\$8,888.00
43	50	LF	ROCK FILTER DAMS (TYPE1-50).	\$25.00		\$1,250.00
44	111	SY	EROSION CONTROL MATTING.	\$7.00		\$777.00
45	1	LS	TREE PROTECTION INCLUSIVE OF LEVEL I, IIA, IIB PROTECTION AND BARK MULCH FOR ROOT ZONE PROTECTION.	\$23,000.00		\$23,000.00
46	1	LS	TREE AND ROOT PRUNING BY CERTIFIED ARBORIST	\$20,000.00		\$20,000.00
47	2	EA	TREE TRANSPLANTING. TREES,10" DIA.	\$2,000.00		\$4,000.00
48	1	LS	PROTECT, SUPPORT, AND/OR TEMPORARILY RELOCATE ELECTRICAL CONTROL PANEL RACK AND POWER POLES (AT LINE C, APPROXIMATE STA. 25+35).	\$5,000.00		\$5,000.00
<b>SUBTOTAL BASE BID</b>						<b>\$4,646,661.30</b>

Prepared by DYS Solicitation No.: B-13-CD-074-RA Contract No.: C-13-CD-062-RA <b>SAN ANTONIO WATER SYSTEM</b> P. O. BOX 2449 SAN ANTONIO, TEXAS 78298-2449 <b>TABULATION OF BIDS</b> PROPOSAL: Olmos Basin Central Watershed Sewer Relief Line (C-3): Line C TIME & Job # 08-2512 10:00 A.M. DATE: November 19, 2013				<b>BID REJECTED</b>  S J Louis Construction of Texas LTD 9862 Lorene #200 San Antonio, Texas 78216		
Item No.	Estimate Qty	Unit of Issue	Description	Unit Price		
49	1	LS	Mobilization		9.50%	\$441,432.82
50	1	LS	Preparing Right-of-Way		4.50%	\$209,099.76
			<b>MOBILIZATION AND PREPARING ROW SUB-TOTAL</b>			<b>\$650,532.58</b>
			<b>TOTAL BID AMOUNT</b>			<b>\$5,297,193.88</b>
CALENDAR DAYS TO COMPLETE						540

[1]