

Prepared by GC

Solicitation No.: B-13-CD-076-DB Contract No.: C-13-CD-000-DB

**SAN ANTONIO WATER S.Y.STEM**

P. O. BOX 2449  
SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL: 13-4808 S. Flores St. 48-inch and 60-inch Outfall Rehab Project

Job No 13-4808

TIME & DATE: 10:00 A.M.

November 18, 2013

**BID REJECTED**  
IPR South Central LLC  
3355 SE Loop 410  
San Antonio, Texas 78222

Item No.	Quantity	Unit of Issue	Description	Unit Price	Total
202.1	106	GAL	Prime Coat	\$8.00	\$848.00
203.1	53	GAL	Tack Coat	\$8.00	\$424.00
205.4	530	SY	Hot Mix Asphaltic Pavement, Type D (3" Pavement Thickness)	\$50.00	\$26,500.00
208.1	530	SY	Salvaging, Hauling, and Stockpiling Reclaimable Asphaltic Pavement (3" Depth)	\$75.00	\$39,750.00
511.3	50	SY	Replacing with Hot Mix Asphaltic Concrete Pavement (3" Type D & 10" Type B)	\$175.00	\$8,750.00
530.1	1	LUMP SUM	Barricades, Signs and Traffic Handling	\$55,000.00	\$55,000.00
540	1	LUMP SUM	Temporary Erosion, Sedimentation and Water Pollution Prevention and Control	\$10,000.00	\$10,000.00
851	2	EA	Adjusting Existing Manholes	\$7,500.00	\$15,000.00
852.1	2	EA	Sanitary Sewer Manhole (0'-6")	\$24,000.00	\$48,000.00
852.3	6	VF	Extra Depth Manholes (>6')	\$1,000.00	\$6,000.00
855	10	EA	Reconstruction of Existing Manholes	\$7,500.00	\$75,000.00
864	1	LUMP SUM	Bypass Pumping	\$900,000.00	\$900,000.00
865	2267	LF	Sewer Main Television Inspection (42" through 48" Diameter)	\$12.00	\$27,204.00
865	598	LF	Sewer Main Television Inspection (54" through 60" Diameter)	\$12.00	\$7,176.00
868.1	2267	LF	Sewer Main Cleaning - Normal (42" through 48" Diameter)	\$22.00	\$49,874.00
868.1	598	LF	Sewer Main Cleaning - Normal (54" through 60" Diameter)	\$30.00	\$17,940.00
901.1	2267	LF	Install 48" CIPP Sanitary Sewer Pipe, all depths	\$328.00	\$743,576.00
901.1	33	LF	Install 54" CIPP Sanitary Sewer Pipe, all depths	\$1,440.00	\$47,520.00
901.1	565	LF	Install 58" CIPP Sanitary Sewer Pipe, all depths	\$575.00	\$324,875.00
910.1	90	VF	Manhole Rehabilitation	\$325.00	\$29,250.00
910.2	50	SF	Sewer Structure Rehabilitation (Non-circular Manholes)	\$30.00	\$1,500.00
1103.3	5	EA	Obstruction Removal by Remote Device, 48" Diameter, all depths	\$1,000.00	\$5,000.00
1103.3	2	EA	Obstruction Removal by Remote Device, 58" Diameter, all depths	\$1,000.00	\$2,000.00
1103.3	1	EA	Obstruction Removal by Person Entry, all depths	\$3,000.00	\$3,000.00
1109	12	EA	Service Reconnection, all depths (person entry)	\$1,000.00	\$12,000.00
	1	EA	Sanitary Sewer Structure Opening	\$25,000.00	\$25,000.00
<b>Bid Summary LINE ITEM "A"- SUBTOTAL SAWS JOB NO. 13-4808 (SEWER):</b>					<b>\$2,481,187.00</b>
<b><u>MOBILIZATION AND PREPARING RIGHT-OF-WAY</u></b>					
Item No.	Quantity	Unit of Issue	Description	Unit Price	Total
100	1	LUMP SUM	MOBILIZATION Percent of the Line Item "A" Subtotal Base Bid written in words _____Percent (Maximum of 10% of the Line Item "A" Sub-total Base Bid amount)	3.0%	\$74,435.61
101	1	LUMP SUM	PREPARING R.O.W. Percent of the Line Item "A" Subtotal Base Bid written in words _____Percent (Maximum of 5% of the Line Item "A" Sub-total Base Bid amount)	1.0%	\$24,811.87
<b>Mobilization &amp; Preparing ROW Sub Total</b>					<b>\$99,247.48</b>
<b>Total Bid Amount (Sum of Line Item "A", Mobilization &amp; Preparing R.O.W.)</b>					<b>\$2,580,434.48</b>
<b>CALENDAR DAYS TO COMPLETE</b>					90