# Dos Rios WRC Electrical System Improvements – Phase 1 Project

#### Jeff Ray, EIT

Project Engineer, Treatment & Recycle Engineering

February 26, 2014



#### Introduction

- Sign attendance sheet
- Owner:
  - Jeff Ray Project Engineer
    SAWS Treatment & Recycle Engineering
  - Marc Ripley Contract Administrator SAWS Contracting

### **RFQ Schedule**

Questions Due

February 27, 2014

Proposals Due

March 11, 2014

**Notification** 

April 2014













Answers Posted

March 4, 2014

Interviews (if necessary)

April 2014

SAWS Board Award

June 2014



#### **Point of Contact for Questions**

#### **Marc Ripley – Contract Administrator**

Fax: 210-233-3136

E-Mail: mripley@saws.org

**Contracting Department** 

2800 US HWY 281 N. San Antonio, TX 78212

**Note**: SAWS Project Managers and Engineers will not respond to any questions submitted by phone and / or email directly to them

#### **Evaluation Criteria**

- Project Team Resumes and Experience in Similar Projects – 40 Points
- Project Approach 30 Points
- QA / QC and Risk Management 15 Points
- SMWB Participation 15 Points

## Dos Rios WRC Facility - Location Map







#### **Motor Control Center – Outdoor**



480 V, 1,000 A (NEMA 1 Enclosure)





#### Motor Control Center – Outdoor, Cont.



480 V, 1,000 A (NEMA 1 Enclosure)





### Motor Control Center - Indoors (Typ.)



480 V, 600 A





## **Generator / Switchboard (Typ.)**






480 V, 762 KVA

480 V, 2,000 A

## Generator / Switchboard (Typ.), Cont.





480 V, 500 KVA


480 V, 2,000 A

Page 11



## Substation (Typ.)







13.2 KV / 480 V, 1,000 KVA

### Pad Mount Transformer (Typ.)



(2) 13.2 KV / 480 V, 500 KVA



13.2 KV / 480 V, 1,000 KVA



#### **Overhead Feeders**



Dual 13.2 KV Overhead Feeder Circuits



Dual 13.2 KV Overhead Feeder / Metering Circuits

Not part of Consultant's 2012 evaluation project





#### **Scope Items**

- Replace 480 V MCCs
  - Some housed in NEMA 1 enclosures only and will require new buildings
  - MCCs at Primary Clarifiers to be replaced
  - Approximately (16) MCC lineups for replacement
- Replace 480 V generators and associated switchboards
  - > Approximately (4) generators / (2) Switchboards for replacement

Scope Items, Cont.

- Replace plant substations 13.2 KV-4.16 KV and 13.2 KV-480 V transformers and associated switches and/or breakers
  - Approximately (3) substations for replacement
- Replace plant 13.2 KV-480 V pad mounted transformers and associated switches and/or breakers
  - Approximately (2) pad mount transformers for replacement



Scope Items, Cont.

- Replace SAWS owned 13.2 KV overhead service feeders including poles and pole mounted appurtenances downstream of plant CPS Energy substation, and add air switch to one overhead circuit
- Replace power, control and instrumentation cable as related to these electrical equipment replacements

Scope Items, Cont.

- Replace RIO controllers for DCS as related to these electrical equipment replacements
- Evaluate/investigate controls, vibration monitoring system, electrical gear, and associated RIOs for three 4,106 V, 3,000 Hp and two 4,160 V, 1,500 Hp blowers
- Miscellaneous civil site and improvements work may be required

Scope Items, Cont.

 Coordination critical in design and construction sequencing to maintain continuous plant operations

#### **Additional Information**

- Dos Rios WRC Electrical System Assessment Project
  - Report finalized 2012
  - Volumes I & V posted on SAWS website
    - Volume I: Electrical / I&C condition evaluation
    - Volume V: Plant one-line diagrams

## Questions



# Dos Rios WRC Electrical System Improvements – Phase 1 Project

#### Jeff Ray, EIT

Project Engineer, Treatment & Recycle Engineering

February 26, 2014

