



## Multiple Sewershed Package 15: Pipe Burst and Open Cut

This project will rehabilitate and replace approximately 2,700 LF of 8, 10, and 24-inch gravity sewer main utilizing pipe burst, pipe jacking, and open cut methods. The sewer mains are located at two locations within the City of San Antonio and near railroad tracks. These locations are in COSA public right of way, private property, and Union Pacific Railroad right of way. One site will include a bore under Union Pacific right of way. This project is part of the work required by San Antonio’s agreement with the U.S. EPA to address sewer infrastructure in need of repair due to condition assessment across the city.

### When Will Work Occur?

Currently scheduled to advertise in summer 2023 and start construction in fall 2023. Estimated overall construction duration is 11 months.

### What to expect:

- ✓ Site 1 will involve 100LF 42” casing to be pipe jacked under UPRR ROW followed by installation of 24” carrier pipe, the remainder of the work at this site being open cut
- ✓ Site 2 will involve pipe bursting and open cut
- ✓ Both sites will involve RailPros coordination and settlement monitoring
- ✓ Both sites will involve sewer bypass
- ✓ Cost estimate is \$2million

For more information:

**SAWS Contracting**  
Diana Woltersdorf  
210-233-3372

Florinda Gonzales  
210-233-3914

