



Sun Valley Reroute Project

SAWS construction work on this project will abandon approximately 130 linear feet of 8-inch sewer mains and reroute approximately 820 linear feet of 8-inch sewer mains within Sun Valley Elementary School. This project is part of the work required by San Antonio's agreement with the EPA to rehabilitate deteriorated sewer infrastructure across the city.

When Will Work Occur?

Estimated construction duration is 6 months.

Construction Elements:

- ✓ Construction on this project will reroute approximately 820 linear feet of 8-inch sewer mains within Sun Valley Elementary School near SW Loop 410 and Sun Valley Dr.
- ✓ Abandonment of approximately 130 linear feet of 8-inch sewer mains.
- ✓ This will address sewer mains in need of repair based on condition assessment and will also rehabilitate or replace associated manholes.
- ✓ Average depth of excavation is 10 feet.

For more information:

SAWS Engineering Manager
Antonio Leyva
210-233-3943

