



## Classen Steubing New Bore Alignment

This project will install approximately 1,550 linear feet of 30-inch sewer pipe, 110 feet of 8-inch sewer pipe, and eliminate two lift stations: #150 and #191. This project includes trenchless installation under a SARA earthen dam and extension of existing sewer main along Hwy 281. This will increase capacity to better serve the area.

### When Will Work Occur?

Estimated construction duration is 12 months.

### Construction Elements:

- Installation of approximately 110 LF of 8-inch and 1,550 LF of 30-inch gravity sewer at depths up to 35-ft in limestone rock via open-cut and trenchless methods
- Involves trenchless excavation underneath a SARA earthen dam
- Elimination of two lift stations
- Coordination with SARA, CoSA, TXDoT and other stakeholders
- The design engineer is Pape Dawson Engineers, Inc.
- The work is in a flood way and within EARZ.

### For more information:

Engineering Manager

Cristina De La Garza

[Cristina.DeLaGarza@saws.org](mailto:Cristina.DeLaGarza@saws.org)

