

**SAN ANTONIO WATER SYSTEM**

P. O. BOX 2449

SAN ANTONIO, TEXAS 78298-2449

**TABULATION OF BIDS**

PROPOSAL FOR: Repair of thirteen (13) Monorail, JIB, and Bridge Cranes located at the Dos Rios Waste Water Treatment Plant

TIME & DATE: 3:00 p.m., May 3, 2013

Bay Area/General Crane Service Co.  
950 Schneider Dr.  
Cibolo, TX 78108

ITEM NO.	DESCRIPTION AND APPROXIMATE QUANTITY				
ITEM 1	<b>Unit #: 1 (Primary Pump #1) - 1/2 Ton Jib Crane</b>		<b>UOM: LS</b>		
	Reattach festoon cable to tagline rings	PRICE	192.50		
	Replace pendant/remote cable	PRICE	565.00		
	Replace electrical from hoist to trolley	PRICE	277.00		
	UNIT REPAIR TOTAL	TOTAL	1,034.50		
ITEM 2	<b>Unit #: 2 (Primary Pump #2) - 1/2 Ton Jib Crane</b>		<b>UOM: LS</b>		
	Replace hinge on hoist control panel	PRICE	348.00		
	UNIT REPAIR TOTAL	TOTAL	348.00		
ITEM 3	<b>Unit #: 3 (Chlorine Room) - 2 Ton Monorail</b>		<b>UOM: LS</b>		
	Replace broken ground bar on conductor system	PRICE	269.50		
	Replace worn out pushbutton station on hoist	PRICE	526.00		
	Replace Pendant/Remote operational decals and legends	PRICE	391.65		
	Replace pendant cord on hoist	PRICE	322.30		
UNIT REPAIR TOTAL	TOTAL	1,509.45			
ITEM 4	<b>Unit#: 4 DO NOT BID</b>				
	Replace Pendant/Remote Grommets	PRICE	DO NOT BID		
	Replace conductor bar system on runway and all associated connectors	PRICE	DO NOT BID		
UNIT REPAIR TOTAL	TOTAL	DO NOT BID			
ITEM 5	<b>Unit #: 5 (Sludge Separator Monorail) - 2 Ton Monorail System</b>		<b>UOM: LS</b>		
	Troubleshoot and replace faulty hoist limit switches	PRICE	1,560.00		
	Replace worn out pushbutton station	PRICE	560.00		
	Reinstall cable into cord connector properly and adjust strain relief cable to prevent pendant cord from coming out	PRICE	283.00		
	UNIT REPAIR TOTAL	TOTAL	2,403.00		
ITEM 6	<b>Unit #: DO NOT BID</b>				
	Replace conductor bar system on runway	PRICE	DO NOT BID		
	Replace C - Track and trolleys with Stainless Steel system to prevent corrosion issues	PRICE	DO NOT BID		
	Replace feed wires from disconnect to power feeds on conductor bar	PRICE	DO NOT BID		
	Replace safety latch on load hook	PRICE	DO NOT BID		
	Replace pushbutton station on bridge crane	PRICE	DO NOT BID		
	UNIT REPAIR TOTAL	TOTAL	DO NOT BID		
ITEM 7	<b>Unit #: DO NOT BID</b>				
	Replace main disconnect on bridge control	PRICE	DO NOT BID		
	Fabricate and install tow arm on festoon system	PRICE	DO NOT BID		
	Replace pushbutton station on hoist	PRICE	DO NOT BID		
	Replace pendant cord on hoist	PRICE	DO NOT BID		
	Replace pendant cord strain relief	PRICE	DO NOT BID		
	Replace incoming power cord from collectors	PRICE	DO NOT BID		
UNIT REPAIR TOTAL	TOTAL	DO NOT BID			
ITEM 8	<b>Unit #: 8 DO NOT BID</b>				
	Re stencil capacity labels	PRICE	DO NOT BID		
	Install metal warning tube, and metal warning tube, and metal warning tag	PRICE	DO NOT BID		
UNIT REPAIR TOTAL	TOTAL	DO NOT BID			
ITEM 9	<b>Unit #: 9 DO NOT BID</b>				
	Replace worn out wire rope on hoist	PRICE	DO NOT BID		
UNIT REPAIR TOTAL	TOTAL	DO NOT BID			
ITEM 10	<b>Unit #: 11 DO NOT BID</b>				
	Replace safety latch on load hook	PRICE	DO NOT BID		
	Install warning tube no charge during next visit	PRICE	DO NOT BID		
UNIT REPAIR TOTAL	TOTAL	DO NOT BID			
ITEM 11	<b>Unit #: 22 (Chlorine Injection) - 1 Ton Monorail System</b>		<b>UOM: LS</b>		
	Remove old conductor bar and reinstall a new 4 bar grounded conductor system	PRICE	2,036.00		
UNIT REPAIR TOTAL	TOTAL	2,036.00			
ITEM 12	<b>Unit #: 25 (O&amp;M Building/Welding Shop)-7.5 Ton Gaffey Bridge - O&amp;M Bldg.</b>		<b>UOM: LS</b>		
	Replace safety latch on load hook	PRICE	28.69		
	Disassemble and repair leaking gearboxes on bridge drives	PRICE	1,871.72		
UNIT REPAIR TOTAL	TOTAL	1,900.41			

**SAN ANTONIO WATER SYSTEM**  
 P. O. BOX 2449  
 SAN ANTONIO, TEXAS 78298-2449  
**TABULATION OF BIDS**

PROPOSAL FOR: Repair of thirteen (13) Monorail, JIB, and Bridge Cranes located at the Dos Rios Waste Water Treatment Plant  
 TIME & DATE: 3:00 p.m., May 3, 2013

Bay Area/General Crane Service Co.  
 950 Schneider Dr.  
 Cibolo, TX 78108

ITEM NO.	DESCRIPTION AND APPROXIMATE QUANTITY				
<b>ITEM 13</b>	<b>Unit #: 26 (Compressor Building) - 30 Ton Zenar Bridge</b>		<b>UOM: LS</b>		
	Replace all conductor bar on runway	PRICE	7,748.00		
	Replace damaged bridge gearbox fasteners	PRICE	165.00		
	Replace festoon trolleys and end clamp on bridge festoon system	PRICE	1,768.00		
	Replace bridge contactor controls with new Variable Frequency Drive Control package	PRICE	8,140.00		
	<b>UNIT REPAIR TOTAL</b>	<b>TOTAL</b>	<b>17,821.00</b>		
			*		
	<b>GRAND TOTAL ITEMS 1-13</b>	<b>TOTAL</b>	<b>27,052.36</b>		
	Terms		Net 30 days		
	Delivery Days				
	<b>*LOW BIDDER</b>				

BIDS MAILED TO AND/OR PICKED UP BY:

- Absolute Crane Service
- Ace Industries
- BayArea/General Crane Service Co.
- Hoist and Crane Service Group
- Konescranes
- Proserv Anchor Crane Group
- Shanco Equipment Specialist

SAWS Website