

- 1. The concrete shall be 4000 psi, min, and reinfocred with No. 4 bars, as shown.
 2. The concrete shall extend to edge of saw cut pavement.
 3. Manhole Ring Encasement is required on all manholes.

PROPERTY OF SAN ANTONIO WATER SYSTEM SAN ANTONIO, TEXAS

MANHOLE RING **ENCASEMENT DETAIL**

AUGUST 2009	FEBRUARY 2017
APPROVED	REVISED

DD-852-03

SHEET of <u>2</u>