



- NOTE:**
1. The concrete shall be 4000 psi, min, and reinforced with 2-No. 4 bars, as shown.
 2. The concrete shall extend to edge of saw cut pavement.
 3. Manhole Ring Encasement is required on all manholes.

PROPERTY OF SAN ANTONIO WATER SYSTEM SAN ANTONIO, TEXAS	MANHOLE RING ENCASEMENT DETAIL DOWNTOWN	APPROVED	REVISED
		DRAFT	FEBRUARY 2017
		DD-852-03	