

CAPACITY, MANAGEMENT, OPERATION, AND MAINTENANCE ALTERNATIVES ANALYSIS

# Project Scoping Report 2022 CMOM Central West Sewershed Project

PREPARED FOR: San Antonio Water System

PREPARED BY: Camille Garza, Steven Anthes and Sean Oboyle

**DATE:** July 19, 2022

| Revision | Date      | Revision Description | Approved By                                       |
|----------|-----------|----------------------|---|
| 0        | 6/16/2022 | Draft Submittal      | Camille Garza, Steven<br>Anthes & Sean Oboyle     |
| 1        | 6/24/2022 | Final Draft QC       | Project Controls, Ann Peche<br>& Rachel Hoffmeyer |
| 2        | 7/19/2022 | Final Submittal      | Ann Peche   |
|          |           |                      |   |
|          |           |                      |   |
|          |           |                      |   |
|          |           |                      |   |
|          | 4         |                      |   |
|          |           |                      |   |

This report is released for the purpose of defining the scope of this project and providing recommendations to be verified during the design phase. This report is not to be used for construction, bidding or permitting purposes.

Ann E. Peche, P.E.

## 1.0 Executive Summary

San Antonio Water System (SAWS) entered into a Consent Decree (CD) with the United States Environmental Protection Agency (EPA) on July 23, 2013. As part of the ongoing Capacity, Management, Operations, and Maintenance (CMOM) component of the CD, SAWS is required to perform alternative analysis on targeted and urgent mains identified as high risk.

This report presents the results of the CMOM alternative analysis for approximately 14,431 linear feet of selected gravity sewer lines. **Table-1.1** summarizes the proposed constructions methods and their estimated costs. The recommendations in this report may be further modified during subsequent design and construction phases, as appropriate, based on additional data and findings.

Type of Work Length Line Size **Estimated** (ft) **Construction Cost** Range (in) **CIPP** 14,407 54 - 72 \$24,902,800.00 **OPEN CUT** 24 24 \$29,900.00 **Total** 14,431 \$24,932,700.00

Table-1.1: Proposed Construction Method and Estimated Costs

### 2.0 Evaluation

Pipe segments chosen to be rehabilitated on this package have contributed to previous SSOs, and/or are likely to cause or significantly contribute to the future of occurrence of SSOs.

#### 3.0 Coordination

#### **Street Projects**

The City of San Antonio (CoSA) provides an ArcGIS layer of street projects throughout the city. **Table-3.1** below lists the pipes that are located near or within identified street projects. This information has also been overlaid into the detailed location maps provided. It is our understanding that the actual dates of the projects are subject to change. It is recommended that SAWS coordinate with CoSA to determine the timing of the street projects during design. Please note that pipes may be required to have the construction expedited where street projects are forthcoming.

Street Location Type of Project

2017-2022 CoSA Bond Project

Table-3.1: Pipes Located on CoSA Improvement Project

Compkey

992066

Broadway St.

#### High and Medium Pavement Condition Index (PCI) Roads

CoSA provides an ArcGIS layer that has the estimated PCI of roads in the city. A majority of mains on this package will be rehabilitated via CIPP but may have an impact on high and medium PCI roads.

#### **Other Considerations**

Pipes located in sensitive areas that may require additional permits have been listed below in **Table-3.3**.

CompkeyReason1026445100 Year Floodplain3907883TxDOT ROW3907884TxDOT ROW

Table-3.3: Pipes that need additional coordination

## 4.0 Planning Budget

The planning budget provided below is based on historical data from similar bids between 2017 and 2021. The data in **Table-4.1** and **Table-4.2** provides cost estimating metrics for the different methods of sewer pipeline rehabilitation and replacement (CIPP, pipe bursting, pipe replacement) for the typical sewer pipe sizes. The unit pricing was calculated based on: pipe size, rehabilitation method, number of estimated point repairs, internal repairs, lateral reconnections, and the pavement condition index of all impacted roads. A contingency of 30% is incorporated into the Estimated Cost Calculation because of the age of the historical data used to calculate the unit pricing. The planning budget should be revised by the Project Design Consultant during the design based on AACE International standards.

| Description    | Quantity        | Unit | Unit Price | Total*           |
|----------------|-----------------|------|------------|------------------|
| 54 – inch CIPP | 3,998.1         | LF   | \$1,010.73 | \$ 4,041,000.00  |
| 60 – inch CIPP | 2,604.9         | LF   | \$1,650.35 | \$ 4,299,000.00  |
| 72 – inch CIPP | 7,804.0         | LF   | \$1,385.96 | \$ 10,816,000.00 |
|                |                 |      | Sub Total  | \$19,156,000.00  |
|                | \$5,746,800.00  |      |            |                  |
|                | \$24,902,800.00 |      |            |                  |

Table-4.1: Estimated CIPP Cost

Table-4.2: Estimated OPEN CUT Cost

| Description        | Quantity    | Unit | Unit Price     | Total*          |
|--------------------|-------------|------|----------------|-----------------|
| 24 – inch OPEN CUT | 24          | LF   | \$958.33       | \$<br>23,000.00 |
|                    |             |      | Sub Total      | \$23,000.00     |
|                    |             | Con  | tingency (30%) | \$6,900.00      |
|                    | \$29,900.00 |      |                |                 |

<sup>\*</sup>Total amounts have been rounded to nearest \$1000.

# 5.0 Planning Recommendation

**Table-5.1** provides detailed information, the preliminary remediation method, as well as the reason behind each method chosen for each pipe segment included in this package.

Table-5.1: Recommendation Summary

| Map No. | Pipe ID | Preliminary<br>Rehabilitation Actions | Diameter | Length | Material | Install Year | Comments   |
|---------|---------|---------------------------------------|----------|--------|----------|--------------|--|
| 10      | 3518078 | CIPP                                  | 60       | 157    | RCP      | 1967         | DS CCTV from 2022 includes MH to MH coverage. Some surface aggregate visible/projecting, but CCTV video becomes blurry half way through. Pipe appeared to be in fair condition during blurry CCTV and is a candidate for CIPP. 2 laterals identified in the CCTV. Segment is located along the C-13 Broadway Corridor Project Pkg B alignment. Segment appears to cross a 24" water main. Propose CIPP due to pipe condition and location.   |
| 10      | 992066  | CIPP                                  | 60       | 301.9  | RCP      | 1967         | DS CCTV from 2019 includes MH to MH coverage with sonar. Surface aggregate visible/projecting. Pipe is a candidate for CIPP. CCTV references old USMH # (45400 instead of 1069927). Segment is located along the C-13 Broadway Corridor Project Pkg B alignment. Segment appears to cross two 6" water mains and an 8" water main. Propose CIPP due to pipe condition and location.  |
| 11      | 1026445 | СІРР                                  | 72       | 1800   | RCP      | 1986         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible/projecting and intruding sealing rings and rags hanging throughout. Pipe is a candidate for CIPP. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. As-built also indicates the main is within a 130LF concrete saddle near the USMH where there is shallow ground coverage and there is a curve in the main near the DSMH. There is a parallel 42" recycle main along the length of the pipe. Sewer mains upstream of this segment are part of Multiple Sewershed Pkg 18 project. Propose CIPP due to pipe size, condition, and location. |
| 12      | 976097  | CIPP                                  | 54       | 1030   | RCP      | 1965         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible/projecting throughout and deposits attached ragging. CCTV shows slight curve in the pipe near the DSMH. Pipe is a candidate for CIPP. As-built indicates main is in a 50' sewer easement. Consultant to confirm easement. There is a parallel 42" recycle main along the length of the pipe. Sewer mains upstream of this segment are part of Multiple Sewershed Pkg 18 project. Propose CIPP due to pipe size, condition, and location.  |
| 12      | 1012763 | CIPP                                  | 72       | 1546.3 | RCP      | 1986         | DS CCTV from 2018 includes MH to MH coverage with sonar. Pipe has reinforcement visible/projecting and intruding sealing rings hanging throughout. The quality of the CCTV is poor/blurry. Pipe is a candidate for CIPP, but new CCTV may be warranted based on age & quality of existing CCTV. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.  |

Table-5.1: Recommendation Summary

| Map No. | Pipe ID | Preliminary<br>Rehabilitation Actions | Diameter | Length | Material | Install Year | Comments   |
|---------|---------|---------------------------------------|----------|--------|----------|--------------|--|
| 12      | 1010738 | СІРР                                  | 54       | 1614   | RCP      | 1965         | DS CCTV from 2018 includes MH to MH coverage with sonar. Pipe has reinforcement visible/projecting and surface aggregate projecting/missing throughout. The quality of the CCTV is poor/blurry. Pipe is a candidate for CIPP, but new CCTV may be warranted based on age & quality of existing CCTV. As-built indicates main is in a 50' sewer easement. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.  |
| 13      | 3907883 | CIPP                                  | 72       | 53.7   | RCP      | 1986         | DS CCTV from 2021 includes MH to MH coverage. Pipe has reinforcement visible/projecting and intruding sealing rings hanging. Pipe is a candidate for CIPP. USMH was installed in 2020 as part of Multiple Sewershed Package 5. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.   |
| 13      | 3907884 | CIPP                                  | 54       | 111.1  | RCP      | 1965         | DS CCTV from 2021 includes MH to MH coverage. Pipe has reinforcement visible/projecting and surface aggregate projecting/missing throughout. Pipe is a candidate for CIPP. USMH was installed in 2020 as part of Multiple Sewershed Package 5. As-built indicates main is in a 50' sewer easement. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.  |
| 14      | 1010672 | CIPP                                  | 72       | 1642   | RCP      | 2003         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible/projecting and surface aggregate projecting/missing throughout. Pipe is a candidate for CIPP. USMH is a doghouse manhole installed in 2020. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. There is also a parallel 42" recycle main. OHE crossing and a power pole is located near the DSMH. Propose CIPP due to pipe size, condition, and location. |
| 14      | 3213786 | CIPP                                  | 54       | 1243   | RCP      | 2003         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible/projecting and deposit attached ragging. Pipe is a candidate for CIPP. As-built indicates main is in a 50' sewer easement. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.   |
| 15      | 1010674 | CIPP                                  | 60       | 496    | RCP      | 2003         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible and surface aggregate missing. Pipe is a candidate for CIPP. Segment appears to cross two gas mains, a 16" water main, OHE, and a concrete drainage channel along Applewhite Rd; segment also runs parallel to a 42" recycle main. Propose CIPP due to pipe size, condition, and location.  |

Table-5.1: Recommendation Summary

| Map No. | Pipe ID | Preliminary<br>Rehabilitation Actions | Diameter | Length | Material | Install Year | Comments   |
|---------|---------|---------------------------------------|----------|--------|----------|--------------|--|
| 15      | 1012710 | CIPP                                  | 72       | 1101.1 | RCP      | 1986         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible/projecting. A section of reinforcement is detached and hanging from the crown of the pipe at about 17ft from the USMH. Pipe is a candidate for CIPP once hanging reinforcement is removed. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. Segment appears to cross two gas mains, a 16" water main, OHE, and a concrete drainage channel along Applewhite Rd; segment also runs parallel to a 42" recycle main. Propose CIPP due to pipe size, condition, and location. |
| 16      | 1010109 | CIPP                                  | 72       | 1660.9 | RCP      | 1986         | DS CCTV from 2022 includes MH to MH coverage. Pipe has surface aggregate visible and areas of reinforcement visible/projecting. Pipe is a candidate for CIPP. As-built indicates main is in a 50' sewer easement that also covers the parallel 54" sewer main. Consultant to confirm easement. There is also a parallel 42" recycle main. Propose CIPP due to pipe size, condition, and location.  |
| 16      | 1021633 | OPEN CUT                              | 24       | 24     | PVC      | 1986         | DS CCTV from 2021 includes MH to MH coverage. Pipe has reinforcement visible, surface aggregate missing, and also appears to have deposit attached encrustation. Pipe could be lined but may require mechanical cleaning. Pipe acts as a balancing line between the 60" main and 72" main. Propose Open Cut due to pipe condition, size, and short segment length.   |
| 16      | 1013129 | CIPP                                  | 60       | 1650   | RCP      | 2003         | DS CCTV from 2021 includes MH to MH coverage and sonar available. Pipe has reinforcement visible and surface aggregate missing. Pipe is a candidate for CIPP. Segment runs parallel to a 42" recycle main. Propose CIPP due to pipe size, condition, and location.   |

# 6.0 Proposed Project Schedule

**Table-6.1** provides a general project schedule which includes a timeframe for engineering design (plans, permits, right-of-entry, etc.), bidding, and construction phases based CIP board funding and previous schedules from similar projects. These should be reviewed and revised by the consultant during the contract negotiation.

# 7.0 Detailed Maps

In the detailed maps attached are the CoSA street projects, the estimated PCI for all CoSA roads, and relevant sensitive areas.

| Tasli Nieres  | Calaradari Da | C++         | Finish       | ble 6.1 - Proposed                                 | <u> </u>  | 1                       |  | 1  |                                  |
|---|---------------|-------------|--------------|--|---|-------------------------|--|--|----------------------------------|
| Task Name   | Calendar Days | Start       | Finish       | 22 3rd Quarter 4th Quarter Jul Aug Sep Oct Nov Dec | 202<br>1st Quarter 2nd Quarter<br>Jan Feb Mar Apr May Jun | 3rd Quarter 4th Quarter | 2024<br>1st Quarter   2nd Quarter   3rd Qua<br>Jan   Feb Mar Apr May Jun   Jul   Aug | rter   4th Quarter   1st Quarter   Sep Oct Nov Dec Jan Feb Mar | 20<br>2nd Quarter<br>Apr May Jun |
| 2022 CMOM Central West Sewershed Project                                | 1170          | Fri 7/29/22 | Fri 10/10/25 |  |   |                         |  |  |                                  |
| 2 Request For Qualifications & Professional Services Contract Execution | 166           | Fri 7/29/22 | Tue 1/10/23  |  | ٦   |                         |  |  |                                  |
| 7 Design  | 610           | Wed 1/11/23 | Wed 9/11/24  |  |   |                         |  | ٦  |                                  |
| 19 Solicitation   | 139           | Thu 9/12/24 | Tue 1/28/25  |  |   |                         |  |  |                                  |
| 20 100% Deisgn - Contracting Review                                     | 22            | Thu 9/12/24 | Thu 10/3/24  |  |   |                         |  |  |                                  |
| 21 Advertisement  | 28            | Fri 10/4/24 | Thu 10/31/24 |  |   |                         |  |  |                                  |
| 22 Board Prep   | 74            | Fri 11/1/24 | Mon 1/13/25  |  |   |                         |  | *  |                                  |
| 23 Board Date   | 1             | Tue 1/14/25 | Tue 1/14/25  |  |   |                         |  |  |                                  |
| 24 Execute Construction Contract  | 14            | Wed 1/15/25 | Tue 1/28/25  |  |   |                         |  |  |                                  |
| 25 Construction   | 255           | Wed 1/29/25 | Fri 10/10/25 |  |   |                         |  |  |                                  |













