



W-9 Upper Leon Creek

The project will address undersized mains, abandon poor condition pipeline segments, and relocate the alignment in order to reduce sanitary sewer overflows in northwest San Antonio as part of work required under the EPA Consent Decree. The project area is located along Leon Creek from 1 mile north of Bandera Road to the confluence at Culebra Creek south of Grissom Road. The proposed improvements are aligned along Leon Creek stream banks and the City of San Antonio (COSA) Leon Creek Greenway Park hike and bike trails.

SAWS has performed extensive coordination with COSA Parks and evaluation of the project alignment in order to minimize impact to COSA Parks Trails, Heritage trees and existing creeks. As a result of this evaluation, it was determined to tunnel approximately 48% of the project length and open cut the rest to minimize the clearing of trees while at the same time placing the new sewer system away from the creek bed as much as possible therefore preventing future damage to the new system.

When Will Work Occur?

Construction is planned to commence in March 2024. Estimated construction duration is 720 days.

Construction Elements:

- Replacement of approximately 21,600 feet of 42- and 48-inch diameter pipe
- Replacement of approximately 1,700 feet of 8-, 12- and 27-inch diameter pipe
- Fiber Reinforced Sewer manholes and related structures

For more information:

SAWS Contract Administration

Lindsay.Esquivel@saws.org

210-233-3409

