



## 2021 CMOM Package 2 (PB and OC)

SAWS construction work on this project will rehabilitate approximately 6,561 LF of 8-inch through 24-inch gravity sewer mains in several locations within multiple Sewersheds. This project is part of the work required by San Antonio's agreement with the EPA to rehabilitate deteriorated sewer infrastructure across the city.

### When Will Work Occur?

Construction is planned for 2024. Estimated construction duration is 365 calendar days.

### Construction Elements:

- ✓ This project will address sewer mains in need of repair based on condition assessment and will also replace associated manholes.
- ✓ Construction of this project will be in multiple Sewersheds within the City of San Antonio.
- ✓ Rehabilitation of approximately 6,561 LF of 8-inch through 24-inch gravity sewer mains via Pipe burst and Open Cut methods.
- ✓ Construction within Private Properties, CoSA and TxDOT right of way.

### For more information:

#### Engineering Contact

Alla Korostyshevsky  
210-233-3447

#### SAWS Public Relations

Cecilia Picazo  
210-233-3750

