



San Joaquin Avenue (Ceralvo/Arboleda to Old Hwy 90) Sewer & Water Project

Rebuilding Sewer and Water Infrastructure in Your Neighborhood

SAWS construction work on South San Joaquin Avenue from Ceralvo/Arboleda to Enrique M. Barrera Parkway, involves the rehabilitation of approximately 2,839 linear feet of 8-inch to 10-inch sewer mains via pipe bursting method and replacement of approximately 6636 linear feet of 6-inch to 8-inch water mains via open-cut method. This project is also a part of the work required by San Antonio’s agreement with the EPA to rehabilitate deteriorated sewer infrastructure across the city.

When Will Work Occur?

Project construction in this location is anticipated to begin early August 2019 with an anticipated completion date late April 2020.

Construction Elements:

- ✓ Construction on this project will run along South San Joaquin Avenue and Arboleda from Ceralvo Street to Enrique M. Barrera Parkway between Council Districts 5 and 6.
- ✓ Installation of approximately 2839 linear feet of 8-inch and 10-inch sewer main via pipe burst and relay of lateral services via open cut.
- ✓ Installation of approximately 6636 linear feet of 6-inch and 8-inch water mains and service reconnections via open cut method. Project will require sidewalk and street restoration trench repair.
- ✓ Project location is within residential and commercial area.
- ✓ S. San Joaquin Avenue is part of the City of San Antonio Street Improvement Projects for 2020.

For more information:

SAWS Contract Administration:

Diana Woltersdorf
210-233-3372

SAWS Public Relations:

Cecilia Picazo
210-233-3750

