

San Antonio Water System Standard Specifications for Construction

ITEM NO. 200

Flexible Base

200.1 DESCRIPTION: This item shall govern a foundation course for surfacing, pavement, or other base courses in conformity with the typical sections shown in the contract documents and to the lines and grades as established by the Engineer.

200.2 REFERENCE STANDARDS: Reference standards cited in this Specification Item No. 200 refer to the current reference standard published at the time of the latest revision date.

1. San Antonio Water System (SAWS):
 - a. Specifications for Water and Sanitary Sewer Construction
 - b. SAWS Materials Specifications
2. City of San Antonio (COSA) Specifications for Construction
3. American Society for Testing and Materials (ASTM) International:
 - a. ASTM C 131/C131M – Standard Test Method for Resistance to Degradation of Small-Size Course Aggregate by Abrasion and Impact in the Los Angeles Machine
 - b. ASTM D 1556 - Density of Soil in Place by the Sand-Cone Method.
 - c. ASTM D 698 - Standard Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort (12.44 ft-lbf/ft³).
 - d. ASTM D 2922 - Test Methods for Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth).
 - e. ASTM D 361 - Test Method for Water Content of Soils and Rock in Place by Nuclear Methods (shallow depth).
 - f. ASTM D 3017 - Test Method for Water Content of Soils and Rock in Place by Nuclear Methods.
 - g. ASTM D 4318 - Test Method for Liquid Limit, Plastic Limit, and Plasticity Index of Soils.
4. Texas Department of Transportation
 - a. TxDOT Tex-101-E - Preparation of Soil and Flexible Base Materials for Testing.
 - b. TxDOT Tex-103-E – Determining Moisture Content in Soil Materials

San Antonio Water System Standard Specifications for Construction

Retained on 1- 3/4 inch sieve	0 %
Retained on No. 4 sieve	45 to 75 %
Retained on No. 40 sieve	60 to 85 %

4. The material passing the No. 40 sieve shall be known as Soil Binder and shall meet the following requirements:

Liquid Limit shall not exceed	40
Plasticity Index shall not exceed	12

5. The crushed stone shall have an abrasion of not more than 40, when subjected to the Los Angeles Abrasion Test.

200.6 CONSTRUCTION METHODS: The flexible base material shall be placed on the approved subgrade, in courses not to exceed 6 inches compacted depth.

1. It shall be the responsibility of the Contractor that the required amount of material be delivered and uniformly spread and shaped.
2. All material shall be removed from the place where it is dumped by cutting into windrows.
3. It shall be sprinkled, spread, shaped, and rolled in proper sequence to prevent segregation and as necessary for required compaction.
4. Upon completion, the surface shall be smooth and in conformity with typical sections and to the established lines and grades.
5. Any deviation in excess of 1/4 inch in cross section and in length of 16 feet measured longitudinally shall be corrected.
6. All irregularities, depressions, or weak spots which develop shall be corrected at no expense to SAWS.
7. Flexible base shall be compacted to a relative dry density of not less than 95% of the maximum dry density as determined in accordance with TxDOT Test Method Tex 113-E.
8. All density tests will be made within 24 hours after compaction operations are completed.
9. Just prior to the placing of any succeeding course of flexible base or surfacing on a previously completed course, the density and moisture of the top 3 inches of flexible base shall be checked and if the test shows the density to be more than 2% below the specified minimum or the moisture content to be more than 3% above or below the optimum, the course shall be reworked as necessary to obtain the specified compaction and moisture content.

San Antonio Water System Standard Specifications for Construction

10. The Contractor shall be responsible for compaction in accordance with the appropriate Specification.
 - a. Compaction tests will be done at one location point randomly selected or as indicated by the SAWS Inspector/Test Administrator.
 - b. The inspector shall determine the depth at which the density test shall be taken.
 - c. All depths shall be considered for testing without a predetermined maximum or minimum
 - d. Test requirements above are indicated as a minimum requirement, but may be subjected to follow more stringent requirements as established by other appropriate agencies (such as COSA Public Works Right of Way Management Plan, etc.)
 - e. Any failed test shall require the Contractor to remove and replace that layer of material to a length 50 feet in both directions from the failed test location.
 - 1) The Contractor will also be required at no cost to SAWS to provide two additional tests at the replaced location where the initial test failed and at one location point, randomly selected or as indicated by the SAWS Inspector/Test Administrator.
 - f. The Contractor shall be responsible for all costs associated with the proctor and density tests, and for providing to SAWS and Consultant, if applicable, verification that necessary compaction levels were achieved.
11. These tests shall be performed by a nationally-accredited, independent testing laboratory.
12. If the material fails to meet the density specified, it shall be reworked as necessary to meet the required density.

200.7 MEASUREMENT: Flexible Base will be measured by the square yard, complete in place, for the thickness specified in the contract documents, or by the cubic yard, complete in place as indicated in the contract documents.

200.8 PAYMENT: This item will be paid for at the contract unit price bid for "Flexible Base" which price shall be full compensation for all work herein specified, including the furnishing, hauling, and placing of all materials, for all water required, and for all equipment, tools, labor, testing, and incidentals necessary to complete the work.

San Antonio Water System Standard Specifications for Construction

- **End of Specification** -